Brightline Renovations

Kitchens · Bathrooms · Basements

QUOTE #BL-2611
Issued October 30, 2026
Valid 30 days

Kitchen renovation — 14 Maple Street

Full remodel of an 11 × 13 ft kitchen: new cabinets on two walls, quartz countertops, an island with seating for three, induction cooktop on a dedicated circuit, under-cabinet lighting and a tiled backsplash. Existing hardwood floor kept.

Scope and price

Item	Details	Price
Demolition & disposal	Remove cabinets, counters, backsplash; protect floors	$1,450
Cabinets	Shaker style, soft-close, 11 base + 8 upper units	$6,800
Island	4 × 6 ft, two drawers, overhang for three stools	$2,100
Countertops	Quartz, 3 cm, eased edge, undermount sink cut-out	$3,900
Electrical	40 A circuit for induction, 6 LED under-cabinet lights	$1,650
Plumbing	Sink and dishwasher hook-up, new shut-off valves	$780
Backsplash	Matte ceramic tile, 32 sq ft, installed	$1,120
Paint & finishing	Walls, ceiling, trim	$640
Total before taxes		**$18,340**

> Appliances are not included. Price assumes the electrical panel has room for a 40 A breaker; if not, a panel upgrade is quoted separately (estimate $1,900–2,400).

Schedule

1. Week 1 — demolition, electrical and plumbing rough-in
2. Week 2 — cabinets and island installed
3. Week 3 — countertop template; fabrication takes 8–10 business days
4. Week 5 — countertops, sink, backsplash
5. Week 6 — lighting, paint, final walkthrough

Payment

Milestone	Share	Amount
Deposit at signature	30 %	$5,502
Cabinets installed	40 %	$7,336
Final walkthrough	30 %	$5,502

Conditions

Two-year warranty on workmanship; manufacturer warranties on cabinets and countertops. Changes to the scope are quoted in writing before work begins. The site is cleaned at the end of each working day.

Brightline Renovations

Client signature and date